

1. MINERALWOLLE DICKE 30mm, BREITE 50cm
GIEBELWAND RINGSUM / HOHLRAUM 30mm
2. FERMACELL POWERPANEL HD 15mm
3. MINERALWOLLE 160mm DICHT 30kg/m³
4. HOLZBALKEN 60x180mm
5. FERMACELL PLATTE 12,5mm
6. PE-FOLIE
7. G-K PLATTE 12,5mm

1. MINERALWOLLE DICKE 30mm BREITE 60cm
GIEBELWAND RINGSUM / HOHLRAUM 30mm
2. FERMACELL POWERPANEL HD 15mm
3. MINERALWOLLE 180mm DICHT 30kg/m3
4. HOLZBALEN 60x180mm
5. FERMACELLPLATTE 12,5mm
6. PE-FOLIE
7. G-K PLATTE 12,5mm

HAUS B

