

Wohnung 17

Wohnen/Essen	$3,88^5 \times 6,44$	= 25,23	
	+ $0,76^5 \times 1,10^5$	= 0,84	
	+ $0,76^5 \times 0,76^5 \times 0,5$	= 0,29	
		<u>26,36</u>	= 26,36 m <sup>2</sup>
Schlafen	$3,51 \times 4,88^5$		= 17,15 m <sup>2</sup>
Gast/Arbeit/ Essen	$2,49 \times 5,13^5$	= 12,79	
	- $0,40 \times 0,40 \times 0,5$	= 0,08	
	+ $0,30 \times 0,40 \times 0,5$	= 0,06	
		<u>12,77</u>	= 12,77 m <sup>2</sup>
Küche	$1,63^5 \times 2,73^5$	= 4,47	
	+ $1,28 \times 1,93^5$	= 2,48	
		<u>6,95</u>	= 6,95 m <sup>2</sup>
Diele	$1,63^5 \times 1,33^5$	= 2,18	
	+ $1,13^5 \times 2,11^5$	= 2,40	
	+ $1,01 \times 0,60$	= 0,61	
	- $0,45 \times 1,00$	= 0,45	
		<u>4,47</u>	= 4,47 m <sup>2</sup>
Bad	$1,76 \times 2,73^5$		= 4,81 m <sup>2</sup>
WC	$0,93^5 \times 1,63^5$		= 1,53 m <sup>2</sup>
Abstellraum	$0,60 \times 0,60$		= 0,36 m <sup>2</sup>
Abstellraum	$0,45 \times 1,00$		= 0,45 m <sup>2</sup>
			<u>74,85 m<sup>2</sup></u>
abzüglich 3 % Putz			<u>2,25 m<sup>2</sup></u>
			<u>72,60 m<sup>2</sup></u>
Loggia über- dachter Teil	$5,40 \times 0,50$	= 2,70	
	- $0,50 \times 0,50 \times 0,5 \times 2$	= 0,25	
		<u>2,45</u>	
	$5,40 \times 1,40$	= 7,56	
	- $0,50 \times 0,50 \times 0,5 \times 2$	= 0,25	
		<u>7,31</u>	
abzüglich überdachter Teil		- 2,45	
		<u>4,86</u>	
	$2,45 \times 0,5$	= 1,23	
	$4,86 \times 0,25$	= 1,22	
		<u>2,45</u>	= 2,45 m <sup>2</sup>
3. Obergeschoß WHG 17 insgesamt			= <u>75,07 m<sup>2</sup></u>